

6692号 市道谷口俊兼線 輪島市門前町谷口地内

上段当初

数量表総括

下段変更

工種	種別	細別		計	備考
延長				0.0	
土工					
	路盤掘削工		107.4	110	
	路床掘削				
	掘削土運搬		107.4	110	
舗装工					
	表層工		1,080.0	1080	
	不陸整正工		6.0	6	
	上層路盤工	t=10	1,074.0	1070	
	下層路盤工	t=19			
撤去工					
	舗装版切断		6.0	6	
	舗装版取壊		1,080.0	1080	
	As殻運搬		1080×0.05	54	
	As殻処分		$1080 \times 0.05 \times 2.35$	127	

数量表総括															
	測点	単距離	幅員	平均幅員	路盤掘削厚	路床掘削厚	路盤掘削標準	路床掘削	掘削土運搬	舗装面積	上層路盤10cm	上層路盤15cm	下層路盤19cm	不陸整正	舗装切断
断面1	No.0.0		3.00												3.0
	No.1.0	1.00	3.00	3.00						3.0				3.0	
	No.359.0	358.00	3.00	3.00	0.10		107.4		107.4	1,074.0	1,074.0				
	No.360.0	1.00	3.00	3.00						3.0				3.0	3.0
	計	360.00					107.4		107.4	1,080.0	1,074.0			6.0	6.0
							110		110	1,100	1,100			6	6

			1080.0	1080	
As取壊し					m2
	1,080.0*0.05=		54.0	54	
As運搬					m3
	1,080.0×0.05×2.35=		126.9	127	
As処分					t