

工 事 名：令和6年災第6036号 市道馬渡清沢線道路災害復旧工事 工事場所：輪島市門前町馬渡地内					数 量 調 書 (1 / 1)	
工 種	規 格	寸 法	単位	数 量	計 算 式	摘 要
土 工						
	掘 削		m3	10	14.31 = 14.31 m3	
	残 土 処 分		m3	10	14.31 = 14.31 m3	
舗 装 工						
	表 層 工	再生密粒度As (20F) t =5cm	m2	63	62.64 = 62.64 m ²	
	不陸整正	粒調碎石 (M-30) t =3cm	m2	5	5.40 = 5.40 m ²	
	上層路盤工	粒調碎石 (M-40) t =15cm	m2	57	57.24 = 57.24 m ²	
	下層路盤工	再生碎石 (RC-40) t=10cm	m2	57	57.24 = 57.24 m ²	
取 壊 工						
	舗装切断工		m	5	5.40 = 5.40 m	
	アスファルト舗装版 破 砕 工		m2	63	62.64 = 62.64 m2	
	アスファルト殻運搬		m3	3	V= 0.05 x 62.64 = 3.13 m3	
	アスファルト殻 処 分 費		t	7	W= 3.13 x 2.35 = 7.36 t	
						輪 島 市

工事場所： 輪島市門前町馬渡地内

土 量 計 算 書

測 点	単距離							上層路盤		下層路盤	舗装版切断	摘 要
		幅 員	平 均	掘削深	掘削土量	路床盛土	舗装面積	不陸整正	t=15cm	t=10cm		
No. 0	—	2.7	—		—						2.70	
No. 1. 0	1. 0	2.7	2.70	0.00	0.00		2.70	2.70				
No. 22. 2	21. 2	2.7	2.70	0.25	14.31		57.24		57.24	57.24		
No. 23. 2	1. 0	2.7	2.70	0.00	0.00		2.70	2.70			2.70	
合 計	23. 2	2.7			14.31	0.00	62.64	5.40	57.24	57.24	5.40	