

[illegible]

鉄筋挿入工削孔長計算書

鉄筋挿入工 掘削径

φ 65

規格

L=5000mm

(必要削孔長L=4700mm)

各区間の土質区分は代表断面と同等として計上する。

地盤区分F、dt1、dt2を礫質土、w-An、R-Tf(Tb)、An-Tf(Tb)、Anを軟岩と区分する。

段数	規格	土質区分	削孔長 (m/本)	本数 (本)	削孔長(計) (m)
1	L=5000mm	礫質土	1.3	20	26.0
		軟岩	3.4		68.0
2	L=5000mm	礫質土	1.3	20	26.0
		軟岩	3.4		68.0
3	L=5000mm	礫質土	1.6	20	32.0
		軟岩	3.1		62.0
4	L=5000mm	礫質土	2.0	21	42.0
		軟岩	2.7		56.7
5	L=5000mm	礫質土	2.3	21	48.3
		軟岩	2.4		50.4
6	L=5000mm	礫質土	2.5	21	52.5
		軟岩	2.2		46.2
7	L=5000mm	礫質土	2.4	21	50.4
		軟岩	2.3		48.3
8	L=5000mm	礫質土	2.3	22	50.6
		軟岩	2.4		52.8
9	L=5000mm	礫質土	2.1	22	46.2
		軟岩	2.6		57.2
10	L=5000mm	礫質土	2.1	22	46.2
		軟岩	2.6		57.2
11	L=5000mm	礫質土	2.2	22	48.4
		軟岩	2.5		55.0
12	L=5000mm	礫質土	2.4	23	55.2
		軟岩	2.3		52.9
13	L=5000mm	礫質土	2.6	23	59.8
		軟岩	2.1		48.3
14	L=5000mm	礫質土	2.8	23	64.4
		軟岩	1.9		43.7
15	L=5000mm	礫質土	2.9	23	66.7
		軟岩	1.8		41.4

16	L=5000mm	礫質土	3.1	24	74.4
		軟岩	1.6		38.4
17	L=5000mm	礫質土	3.2	24	76.8
		軟岩	1.5		36.0
18	L=5000mm	礫質土	3.2	24	76.8
		軟岩	1.5		36.0
19	L=5000mm	礫質土	3.3	24	79.2
		軟岩	1.4		33.6
20	L=5000mm	礫質土	3.3	25	82.5
		軟岩	1.4		35.0
21	L=5000mm	礫質土	3.4	25	85.0
		軟岩	1.3		32.5
22	L=5000mm	礫質土	3.5	25	87.5
		軟岩	1.2		30.0
23	L=5000mm	礫質土	3.5	25	87.5
		軟岩	1.2		30.0
24	L=5000mm	礫質土	3.6	26	93.6
		軟岩	1.1		28.6
25	L=5000mm	礫質土	3.7	26	96.2
		軟岩	1.0		26.0
26	L=5000mm	礫質土	3.8	26	98.8
		軟岩	0.9		23.4
27	L=5000mm	礫質土	3.8	26	98.8
		軟岩	0.9		23.4

624

集計		(m)
土質	削孔長	1本あたり平均
礫質土	1751.8	2.8
軟岩	1181.0	1.9
合計	2932.8	4.7